



- NOTES:**
1. CONTRACTOR SHALL RESET ALL EXISTING LANDSCAPING WITHIN LIMITS OF DITCH GRADING TO THE EDGE OF DITCH IN KIND.
 2. ALL DRIVEWAY ACCESSES SHALL REMAIN OPEN DURING CONSTRUCTION. CONTRACTOR SHALL COORDINATE WITH PROPERTY OWNERS PRIOR TO ANY DRIVEWAY WORK.
 3. CONTRACTOR TO DETERMINE THE LOCATION OF ALL UNDERGROUND UTILITIES AND COORDINATE ANY CONFLICTS WITH THE ENGINEER.
 4. ALL DISTURBED AREAS OUTSIDE THE ROAD SHALL BE SEEDED WITH A 50/50 COMBINATION OF SHORT DRY GRASS MIX AND NATIVE HIGH COUNTRY GRASS MIX. SEE SPECIFICATIONS FOR MORE DETAIL.
 5. SURVEY OBTAINED IN 2016. CONTRACTOR SHALL VERIFY SITE CONDITIONS PRIOR TO CONSTRUCTION.

PLOTTER: 6/5/2023 10:34:47 PM; FILE: \\S01\19-219\DWG\CAL - TOWN OF BLUE RIVER\CAD\2023 SHERWOOD FOREST MAINTENANCE PROJECT CONCEPT DRAWINGS\11-008-14_PLAN.DWG

PREPARED UNDER THE SUPERVISION OF DESIGNED: WAM DRAWN: MAB CHECKED: ALR	<h1>DRAFT</h1>	SHEET REVISIONS <table border="1"> <thead> <tr> <th>NO.</th> <th>DATE</th> <th>DESCRIPTION</th> <th>BY</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>			NO.	DATE	DESCRIPTION	BY																	 <p>MULLER ENGINEERING COMPANY 777 S. WADSWORTH BLVD. 4-100 LAKEWOOD, COLORADO 80226</p>	 <p>TOWN OF BLUE RIVER</p>	SHERWOOD FOREST MAINTENANCE DATE: 6/5/2023
		NO.	DATE	DESCRIPTION	BY																						
PROJECT NO. 11-008.14	CONCEPT PLAN	DRAWING NO.: C-1 SHEET NO.: X OF X																									